


AD-A155 030 THE REACTION OF PERFLUOROPOLYALKYLETHER OIL WITH FEF(3) 1/1  
ALF(3) AND ALCL(3.. (U) AEROSPACE CORP EL SEGUNDO CA  
CHEMISTRY AND PHYSICS LAB D J CARRE ET AL. 01 APR 85  
UNCLASSIFIED TR-0084A(5945-03)-4 SD-TR-85-11 F/G 7/4 NL



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A155 030

REPORT SD-TR-85-11

(2)

# The Reaction of Perfluoropolyalkylether Oil with $\text{FeF}_3$ , $\text{AlF}_3$ , and $\text{AlCl}_3$ at Elevated Temperatures

D. J. CARRÉ and J. A. MARKOWITZ  
Chemistry and Physics Laboratory  
Laboratory Operations  
The Aerospace Corporation  
El Segundo, CA 90245

1 April 1985

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED

DTIC  
ELECTE  
JUN 17 1985  
A

DTIC FILE COPY


Prepared for  
SPACE DIVISION  
AIR FORCE SYSTEMS COMMAND  
Los Angeles Air Force Station  
P.O. Box 92960, Worldway Postal Center  
Los Angeles, CA 90009-2960


85 5 23 125

This report was submitted by The Aerospace Corporation, El Segundo, CA 90245, under Contract No. F04701-83-C-0084 with the Space Division, P.O. Box 92960, Worldway Postal Center, Los Angeles, CA 90009-2960. It was reviewed and approved for The Aerospace Corporation by S. Feuerstein, Director, Chemistry and Physics Laboratory. Second Lieutenant Buford W. Shipley, Jr., SD/YDEA, was the project officer for the Mission-Oriented Investigation and Experimentation (MOIE) program.

This report has been reviewed by the Public Affairs Office (PAS) and is releasable to the National Technical Information Service (NTIS). At NTIS, it will be available to the general public, including foreign nationals.

This technical report has been reviewed and is approved for publication. Publication of this report does not constitute Air Force approval of the report's findings or conclusions. It is published only for the exchange and stimulation of ideas.

  
Buford W. Shipley, 2nd Lt, USAF  
Project Officer

  
Joseph Hess, GM-15, Director, West Coast  
Office, AF Space Technology Center

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER SD-TR-85-11	2. GOVT ACCESSION NO. AD-A155 030	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle)  The Reaction of Perfluoropolyalkylether Oil with FeF <sub>3</sub> , AlF <sub>3</sub> , and AlCl <sub>3</sub> at Elevated Temperatures		5. TYPE OF REPORT & PERIOD COVERED
		6. PERFORMING ORG. REPORT NUMBER TR-0084A(5945-03)-4
7. AUTHOR(s)  D. J. Carré and J. A. Markowitz		8. CONTRACT OR GRANT NUMBER(s)  F04701-83-C-0084
9. PERFORMING ORGANIZATION NAME AND ADDRESS  The Aerospace Corporation El Segundo, CA 90245		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS Space Division Los Angeles Air Force Station Los Angeles, CA 90009-2960		12. REPORT DATE 1 April 1985
		13. NUMBER OF PAGES 24
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report)  Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Acyl fluorides                      HPLC                      Thermal degradation, Asperity contact temperature      IR Bearings                              Ketones Ferric fluoride                      Lubricant degradation GPC                                      Perfluoropolyalkylether oil		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The interaction of perfluoropolyalkylether (PFPE) oil with ferric fluoride (FeF <sub>3</sub> ) and other Lewis acids at elevated temperatures under inert atmosphere was investigated to determine whether the reaction results in lubricant degradation. At 350°C, ~ 25°C below the onset of thermal degradation, PFPE's reaction with FeF <sub>3</sub> yields acyl fluoride and ketone degradation products and also a decrease in the oil's number average molecular weight.		

DD FORM 1473  
(FACSIMILE)

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

19. KEY WORDS (Continued)

20. ABSTRACT (Continued)

In the presence of small quantities of water, the acyl halide products hydrolyze, resulting in carboxylic acids. The oil's reaction with aluminum fluoride at 350°C and aluminum chloride at 200°C also causes it to degrade measurably. The results indicate that PFPE oil can degrade at estimated bearing asperity contact temperatures in the presence of  $\text{FeF}_3$ .

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

# PREFACE

We thank Dr. P. D. Fleischauer for criticism of the manuscript.

## CONTENTS

PREFACE.....	1
I. INTRODUCTION.....	7
II. EXPERIMENTAL.....	9
A. MATERIALS.....	9
B. EXPERIMENTAL REACTOR.....	9
C. EXPERIMENTAL PROCEDURE.....	9
D. INFRARED SPECTRAL ANALYSIS.....	11
E. CHROMATOGRAPHIC ANALYSIS.....	11
III. RESULTS AND DISCUSSION.....	15
A. INFRARED SPECTROSCOPY.....	15
B. GEL PERMEATION CHROMATOGRAPHY.....	20
C. IMPACT ON LUBRICATION.....	24
IV. CONCLUSIONS.....	27
REFERENCES.....	29

Accession For

NTIS GRA&I

ERIC TAB

Unpublished

1970-1971

1972-1973

1974-1975

1976-1977

1978-1979

1980-1981

1982-1983

1984-1985

1986-1987

1988-1989

1990-1991

1992-1993

1994-1995

1996-1997

1998-1999

2000-2001

2002-2003

2004-2005

2006-2007

2008-2009

2010-2011

2012-2013

2014-2015

2016-2017

2018-2019

2020-2021

2022-2023

2024-2025

2026-2027

2028-2029

2030-2031

2032-2033

2034-2035

2036-2037

2038-2039

2040-2041

2042-2043

2044-2045

2046-2047

2048-2049

2050-2051

2052-2053

2054-2055

2056-2057

2058-2059

2060-2061

2062-2063

2064-2065

2066-2067

2068-2069

2070-2071

2072-2073

2074-2075

2076-2077

2078-2079

2080-2081

2082-2083

2084-2085

2086-2087

2088-2089

2090-2091

2092-2093

2094-2095

2096-2097

2098-2099

2100-2101

2102-2103

2104-2105

2106-2107

2108-2109

2110-2111

2112-2113

2114-2115

2116-2117

2118-2119

2120-2121

2122-2123

2124-2125

2126-2127

2128-2129

2130-2131

2132-2133

2134-2135

2136-2137

2138-2139

2140-2141

2142-2143

2144-2145

2146-2147

2148-2149

2150-2151

2152-2153

2154-2155

2156-2157

2158-2159

2160-2161

2162-2163

2164-2165

2166-2167

2168-2169

2170-2171

2172-2173

2174-2175

2176-2177

2178-2179

2180-2181

2182-2183

2184-2185

2186-2187

2188-2189

2190-2191

2192-2193

2194-2195

2196-2197

2198-2199

2200-2201

2202-2203

2204-2205

2206-2207

2208-2209

2210-2211

2212-2213

2214-2215

2216-2217

2218-2219

2220-2221

2222-2223

2224-2225

2226-2227

2228-2229

2230-2231

2232-2233

2234-2235

2236-2237

2238-2239

2240-2241

2242-2243

2244-2245

2246-2247

2248-2249

2250-2251

2252-2253

2254-2255

2256-2257

2258-2259

2260-2261

2262-2263

2264-2265

2266-2267

2268-2269

2270-2271

2272-2273

2274-2275

2276-2277

2278-2279

2280-2281

2282-2283

2284-2285

2286-2287

2288-2289

2290-2291

2292-2293

2294-2295

2296-2297

2298-2299

2300-2301

2302-2303

2304-2305

2306-2307

2308-2309

2310-2311

2312-2313

2314-2315

2316-2317

2318-2319

2320-2321

2322-2323

2324-2325

2326-2327

2328-2329

2330-2331

2332-2333

2334-2335

2336-2337

2338-2339

2340-2341

2342-2343

2344-2345

2346-2347

2348-2349

2350-2351

2352-2353

2354-2355

2356-2357

2358-2359

2360-2361

2362-2363

2364-2365

2366-2367

2368-2369

2370-2371

2372-2373

2374-2375

2376-2377

2378-2379

2380-2381

2382-2383

2384-2385

2386-2387

2388-2389

2390-2391

2392-2393

2394-2395

2396-2397

2398-2399

2400-2401

2402-2403

2404-2405

2406-2407

2408-2409

2410-2411

2412-2413

2414-2415

2416-2417

2418-2419

2420-2421

2422-2423

2424-2425

2426-2427

2428-2429

2430-2431

2432-2433

2434-2435

2436-2437

2438-2439

2440-2441

2442-2443

2444-2445

2446-2447

2448-2449

2450-2451

2452-2453

2454-2455

2456-2457

2458-2459

2460-2461

2462-2463

2464-2465

2466-2467

2468-2469

2470-2471

2472-2473

2474-2475

2476-2477

2478-2479

2480-2481

2482-2483

2484-2485

2486-2487

2488-2489

2490-2491

2492-2493

2494-2495

2496-2497

2498-2499

2500-2501

2502-2503

2504-2505

2506-2507

2508-2509

2510-2511

2512-2513

2514-2515

2516-2517

2518-2519

2520-2521

2522-2523

2524-2525

2526-2527

2528-2529

2530-2531

2532-2533

2534-2535

2536-2537

2538-2539

2540-2541

2542-2543

2544-2545

2546-2547

2548-2549

2



## FIGURES


1.	Nickel 200 autoclave reactor insert.....	11
2.	FTIR spectra of the reaction products of perfluoro- polyalkylether with Lewis acid catalysts.....	16
3.	Typical GPC trace.....	21
4.	GPC traces generated by subtracting the trace for the standard oil from the sample oil traces.....	25

## TABLES

1.	Perfluoropolyalkylether oil properties.....	10
2.	Sample test conditions.....	12
3.	Infrared absorption-band assignments.....	17
4.	Reaction product GPC data.....	23

## I. INTRODUCTION

Perfluoropolyalkylether (PFPE) oils (I) and oil-based greases are being used with increasing frequency in spacecraft systems because of their favorable properties, which include a wide application temperature range, good viscosity index, and general chemical inertness. The chemical inertness, however, must be evaluated in the light of extended satellite mission lifetimes and the rigors of operation in the orbital environment.



$R_f$  and  $R_f'$  = perfluoropolyalkylether end groups of unspecified length;  $n \approx 20$ .

In studies performed in terrestrial environments, PFPE oils, although considered unreactive, have been observed to react under certain conditions. Under oxidizing conditions and in the presence of ferrous and titanium alloys at elevated temperatures ( $>260^\circ\text{C}$ ), PFPE oils degrade and cause metal to corrode by forming reactive degradation products.<sup>1,2</sup> When PFPE and other fluorinated ethers reacted with the Lewis acid aluminum chloride ( $\text{AlCl}_3$ ) at moderate temperatures ( $\sim 170^\circ\text{C}$ ), the resulting cleavage of the etherate linkage yielded ketone and acid halide degradation products.<sup>3-5</sup>

In our laboratories, tests of a PFPE-oil-based grease thickened with tetrafluoroethylene telomer were performed using 3.175 mm (1/8 in.) bore, 5R 2H, phenolic retainer miniature bearings; they were run at ambient temperature, 48.8 rpm, 22.25 N radial load, 11.12 N axial load, and  $\sim 8 \times 10^{-7}$  Pa test pressure. After  $5 \times 10^6$  revolutions, the bearings were disassembled and examined. Underneath a layer of tetrafluoroethylene telomer that had been burnished on the raceways, the raceway surfaces were extensively pitted,

indicating that chemical/physical degradation had occurred in the system. Auger analysis of the raceway surfaces revealed the presence of fluorine. Clearly, nonoxidative degradation of the grease had occurred.

Based on those observations, a mechanism was hypothesized to explain the lubricant degradation. The steps in the proposed mechanism are: 1) interaction between fluorocarbon and steel surfaces to form ferric fluoride ( $\text{FeF}_3$ ) followed by 2) degradation of the PFPE oil through its reaction with the  $\text{FeF}_3$  analogous to reactions of PFPE with  $\text{AlCl}_3$ . Step 1, interaction of fluorocarbon with iron leading to dehalogenation of the fluorocarbon, has been observed in systems in which aromatic products are formed, but has not been reported for aliphatic systems.<sup>6</sup> The aromaticity undoubtedly contributes in the reaction energetics by stabilizing both the transition state and the products. Whether  $\text{FeF}_3$  was formed in these reactions was not reported; however, its formation is a likely possibility. The formation of metal fluoride compounds has been inferred in the reactions of PFPE oil with aluminum and ferrous alloys under oxygen-containing atmospheres<sup>7</sup> and titanium under oxygen and nitrogen.<sup>8</sup>

This report discusses one aspect of the PFPE-based lubricant-degradation mechanism: the reaction of PFPE oil with  $\text{FeF}_3$ .

## II. EXPERIMENTAL

### A. MATERIALS

The PFPE oil used was a hexafluoropropylene oxide polymer that was treated to remove the reactive end groups. The properties of the oil are listed in Table 1. The Lewis acids  $\text{FeF}_3$ , aluminum fluoride ( $\text{AlF}_3$ ), and  $\text{AlCl}_3$  were anhydrous and were used as received. The solvent was 1,1,2-trichloro-1,2,2-trifluoroethane (Freon TF) and was used as received.

### B. EXPERIMENTAL REACTOR

The reactions of PFPE oil with Lewis acids were run in a recirculating autoclave system because of anticipated high reaction temperatures. Since reaction with ferrous alloys is a potential problem, a small, all-nickel-200 autoclave insert was fabricated (Fig. 1). PFPE fluids do not react significantly with nickel at the temperatures used in this study.<sup>9</sup> A nickel foil gasket or gold wire crush seal was inserted between the top and the base of the reactor to seal the system.

### C. EXPERIMENTAL PROCEDURE

The experimental runs were begun by pipetting the oil into the nickel reactor. Dry nitrogen ( $\text{N}_2$ ) gas was bubbled through the oil for more than 1 h to remove oxygen and water from the oil. While  $\text{N}_2$  gas was passed over the surface of the reactor, the appropriate quantity of Lewis acid catalyst was added and the resulting slurry was stirred to achieve homogeneity. The reactor seal and lid were positioned and securely tightened. The nickel reactor was placed in the autoclave, and the appropriate thermocouples were attached. The autoclave was covered and sealed, then purged internally with dry  $\text{N}_2$  gas at 207 to 276 kPa (30-40 psi). The gas pressure was maintained at >207 kPa (30 psi) during the course of the experimental runs. The autoclave was heated to the desired temperature and maintained at that temperature until the end of the run. After cooling, the autoclave was opened, and the nickel reactor was removed and opened. The slurry was centrifuged to remove the oil portion from the catalyst, and the remaining catalyst was extracted with Freon

TABLE 1. PERFLUOROPOLYALKYLETHER OIL PROPERTIES

Viscosity, cSt	
-18°C	6 900
38°C	85
Viscosity index	113
Pour point, °C	-43
Density, Mg·m <sup>-3</sup>	
24°C	1.89
99°C	1.76
Approximate boiling range, °C at 107 Pa	227-251
Refractive index, n <sub>D</sub> <sup>25</sup>	1.300
Number average molecular weight	~3 700

to remove the remaining soluble oil and products. No capture of volatile reaction products was attempted, even though such products were clearly present in some of the runs. The experimental conditions are given in Table 2.




Fig. 1. Nickel 200 autoclave reactor insert.

#### INFRARED SPECTRAL ANALYSIS

The oil and oil-degradation products were examined spectrally using a Fourier transform infrared spectrophotometer (FTIR). The samples were analyzed neat, between salt plates. The data storage and manipulation capability of the FTIR system enabled the absorptions due to the unreacted oil to be subtracted and the small signals caused by the degradation products to be detected.

#### CHROMATOGRAPHIC ANALYSIS

The liquid products were analyzed by high-performance liquid chromatography (HPLC) in the gel permeation chromatography (GPC) mode. The run conditions and instrument parameters were as follows: The columns, two 125 Å

ive products, acyl halides, would react with the metal surfaces, thereby easing the pitting of the surfaces and providing more sites for reaction. The surface degradation could result in torque anomalies and increased bearing noise. The decrease in MW would result in decreased oil viscosity and increased oil volatility, which would affect the properties of the lubricant film as a function of reaction extent. In our 24 h tests at 350°C, approximately 10 to 15 percent of the oil was converted to lower MW in runs 4 and 10 (350°C) and 20 to 25 percent in runs 3 and 9 (Fig. 4)—substantial percentages. Further reaction would result in continued lowering of oil MW, with attendant changes in lubricity.

It is difficult to estimate the rate at which such changes would occur in actual bearing systems, since asperity contact temperatures and frequency of contacts are not well known for the various bearing materials. Also, the rate depends on load, speed, surface finish, and other parameters. However, the possibility that PFPE-oil-based lubricants can degrade must be considered by spacecraft planners.




Fig. 4. GPC traces generated by subtracting the trace for the standard oil from the sample oil traces: (a) run 3,  $\text{FeF}_3$ ,  $350^\circ\text{C}$ ; (b) run 4,  $\text{FeF}_3$ ,  $350^\circ\text{C}$ ; (c) run 9,  $\text{AlF}_3$ ,  $350^\circ\text{C}$ ; (d) run 10,  $\text{AlCl}_3$ ,  $200^\circ\text{C}$ ; (e) run 5,  $\text{FeF}_3$ ,  $375^\circ\text{C}$ .



with considerable oil degradation. Both runs 9 and 10 exhibit broadening and increases in lower MW components.

The GPC data were also treated by normalizing the areas under the peaks, subtracting the standard peak from those of the samples of interest, and plotting the difference against the retention time. The curves, presented in Fig. 4 for runs 3, 4, 5, 9, and 10, indicate the extent of conversion of PFPE to lower MW products. The negative, or downward-pointing, lobe is proportional to the quantity of PFPE lost, whereas the positive, or upward-pointing, lobe is proportional to increased quantities of lower MW materials. The behavior of the curve for run 5 is the most extreme, indicating a complete conversion of the original oil to degradation products. The curves for the other runs show significant, but much smaller, effects.

The relative intensities of the infrared data, Fig. 2, do not appear to correlate strongly with those of the GPC data, Fig. 4. The products in run 10 give five strong IR bands but do not exhibit a large change in molecular weight. One can only speculate that, at the lower temperatures in run 10, the cleavage reactions are occurring at the ends of the polymer chains and, as a result, there is not a substantial MW shift for the large fragments; whereas the lower MW fragments are sufficiently volatile to be lost. For the other runs, 3 through 5 and 9, the higher temperatures may have resulted in more cleavage toward the centers of the polymer chains, but more data are needed for certainty. The infrared and gel permeation chromatography data clearly indicate that reaction has occurred in runs 3, 4, 5, 9, and 10.

#### IMPACT ON LUBRICATION

PFPE fluids are degraded in the presence of  $\text{FeF}_3$  at elevated temperatures. From an applications standpoint, this result signifies that, although the degradation temperatures are high ( $\sim 350^\circ\text{C}$ ), they are still below that at which thermal degradation occurs ( $\sim 380^\circ\text{C}$ ). Given that contact junction temperatures have been estimated to be as high as  $350^\circ\text{C}$ ,<sup>23</sup> lubricant degradation could be system-life-limiting.

Oil degradation is manifested by the formation of chemically reactive products and the lowering of the residual oil's molecular weight. The

TABLE 4. REACTION PRODUCT GPC DATA\*

RUN NUMBER	PEAK MAXIMUM RETENTION TIME, min	PBV <sup>†</sup>	MOLECULAR WEIGHT AT A <sup>‡</sup>	MOLECULAR WEIGHT AT B <sup>‡</sup>
1	16.59	1.07	3672	2611
2	16.57	0.91	3715	2604
3	16.77	1.55	3309	2139
4	16.58	1.35	3693	2544
5	17.78	0.68	1846	1452
6	16.58	1.01	3693	2626
6A	16.59	1.00	3672	2596
7	16.58	1.03	3693	2596
8	16.59	1.03	3672	2596
9	16.68	1.44	3486	2313
10	16.59	1.58	3672	2374
Standard <sup>§</sup>	16.59	1.00	3672	2641

\*Each value represents an average of two chromatograms of the same material. Variations were insignificant.

<sup>†</sup>PBV = peak broadening value (see text).

<sup>‡</sup>See Fig. 4.

<sup>§</sup>Unused oil.

The normalized values were then divided by the normalized value for the standard unused oil, resulting in a set of peak-broadening values (PBVs) that are internally normalized. The normalization operation is given by the following equation:

$$\text{Normalized PBV} = \frac{(\text{FWHM})_x}{\text{Height}_x} \div \frac{(\text{FWHM})_s}{\text{Height}_s}$$

where the subscripts x and s correspond to the sample of interest and the standard oil, respectively. The resulting normalized values are listed in Table 4.

The GPC traces can be quantitated by correlating retention time (RT) with MW. Regions in which the log MW is linear with RT for various GPC columns have been observed.<sup>20-22</sup> For the specific columns used in this study, the linear region of the plot is from MW ~ 20 000 down to ~ 1 000.<sup>22</sup> No suitable MW standards were available for the solvent and solute classes used, so a two-point calibration curve was constructed. The unreacted PFPE oil, investigated here, with a number average MW of ~ 3 700 (manufacturer's specification) and a different PFPE oil, a tetrafluoroethylene oxide polymer, with a number average MW of ~ 13 500 (manufacturer's specification) were used as the two standards. Because of batch-to-batch variations in the oils, those values are only approximate (good to ±10 percent) but serve as a guide so that trends can be established. The calibration curve is described by the following equation:

$$\log \text{MW} = - 0.251\text{RT} + 7.729$$

The MW values for the points marked A and B in Fig. 3 were calculated using the above equation for each sample (see Table 4) and were used for comparison. The values listed for runs 1, 2, 6, 6A, 7, and 8 vary little relative to the value for the standard, unused oil. For run 3, the MW values indicate that there has been a shift to lower values as well as a broadening of the peak. Run 4 exhibits some broadening with a slight MW decrease at point B. The run 5 data exhibit a large MW shift. Although the peak is narrower than the standard's, the MW has shifted to much lower values, consistent




Fig. 3. Typical GPC trace: point A is at curve maximum, point B is at FWHM point (see text).

The IR spectrum for run 10 is the most complex of the five spectra. Absorption bands occur at 1806, 1878, and 1886  $\text{cm}^{-1}$ , consistent with the fluorinated acyl fluoride and ketone that were observed in run 3. In addition, there are significant bands at 1789 and 1818  $\text{cm}^{-1}$ , corresponding to acyl chloride products.  $\text{CF}_3\text{COCl}$  absorbs at 1810  $\text{cm}^{-1}$  in the vapor phase<sup>15</sup> and at 1799  $\text{cm}^{-1}$  in the condensed phase.<sup>16</sup> Multiple absorbances would more than likely occur for the acyl chloride products.<sup>12,13</sup>

The observation that absorption bands can be assigned to (II), (III), and acyl chloride in run 10 implies that halide exchange prior to cleavage is not facile. If halide exchange were facile with PFPE, a number of different fluorine- and chlorine-substituted products would be expected that would be spectrally distinguishable. Chlorine substitution would not be favored because fluorine substituents  $\alpha$  to the ether oxygen destabilize the oxonium ion intermediate less than chlorine and would facilitate cleavage. The  $\sigma^+$  values for halide substitution indicate that fluorine provides more stabilization of incipient carbonium ions than do the other halides when direct resonance interaction with the positive carbon is possible.<sup>17,18</sup> The acyl fluorides and acyl chlorides may be the result of halide exchange in the acyl halides. Rapid exchange has been reported for the  $\text{C}_6\text{H}_5\text{COCl} + \text{Al} (^{36}\text{Cl})_3$  system.<sup>19</sup>

#### B. GEL PERMEATION CHROMATOGRAPHY

Figure 3 shows a typical GPC trace. In GPC, the movement of sample molecules is retarded by the packing material, so that the sample components are eluted from the column in order of decreasing molecular size [which is approximately proportional to molecular weight (MW)]; i.e., the lower MW material is on the right in Fig. 3. Changes in the GPC traces as a function of reaction are observed in the retention times of the peak maxima and broadening of the peaks as higher MW materials are depleted and lower MW materials are formed.

The retention time is available directly from the GPC trace; however, the trace broadening is more subtle. Borrowing from spectroscopy, we can use the full width at half maximum (FWHM) as a measure of GPC trace broadening. The FWHM of each trace was divided by the peak height to normalize the broadening.

The IR spectra for runs 4 and 5, aside from one major absorption band in each spectrum, are very similar. Small, unassigned absorption bands appear at 1722 and 1737  $\text{cm}^{-1}$ ; absorptions that correspond to carboxylic acids appear at 1752 and 1777  $\text{cm}^{-1}$ ; and slight absorptions appear at 1806, 1878, and 1886  $\text{cm}^{-1}$ , indicating the possible presence of (II) and (III). The spectral similarities can probably be attributed to the reaction temperatures: For run 5, the reaction temperature was maintained at 375°C; the temperature during run 4, although nominally set at 350°C, exceeded 365°C for several hours.

At higher temperature, thermal degradation can become the predominant pathway. The thermal degradation of PFPE at 380°C under inert atmosphere has yielded  $\text{CF}_3\text{COF}$  and  $\text{COF}_2$ , and other products.<sup>1</sup> The hydrolysis of those products, as well as the hydrolysis of the products from the catalyzed ether cleavage pathway, could cause the strong absorption band at 1766  $\text{cm}^{-1}$  and the bands at 1766 and 1777  $\text{cm}^{-1}$  in the run 5 spectrum. [Significant amounts of water were detected in the run 5 products, whereas one-fourth as much water was detected in the run 4 products. Since it is unreasonable for water to form during the reactions, it must enter during the analytical workup.] Fluorinated carboxylic acids have absorption bands in that spectral region.<sup>13</sup> In contrast, the run 4 spectrum has a strong band at 2052  $\text{cm}^{-1}$ , which could be assigned to an ion pair such as  $\text{FeF}_4^- [\text{R}_f\text{CO}^+]$ . In the reaction of  $\text{AlCl}_3$  with  $\text{CH}_3\text{COCl}$ , absorption at 2193  $\text{cm}^{-1}$  has been assigned to the acylium ion of the ion pair  $\text{AlCl}_4^- [\text{CH}_3\text{CO}^+]$ .<sup>14</sup> Another possibility is a ketene,  $(\text{R}_f)_2\text{C}=\text{C}=\text{O}$ . The species responsible for the 2052  $\text{cm}^{-1}$  absorption can only be speculated at this juncture, however.

The significant IR absorptions for run 9 occur at 1777 and 3618  $\text{cm}^{-1}$ , and have been assigned to fluorinated carboxylic acids<sup>13</sup> and water, respectively. A slight absorption occurs in the spectral region where the fluorinated ketone (III) absorbs. As in run 5, a significant amount of water is present in the products, which would be consistent with hydrolysis of acyl fluorides to form carboxylic acids. That substantial amounts of ketone are lacking in the products of the reaction with the  $\text{AlF}_3$  catalyst indicates that there may be some selectivity in the cleavage reaction that depends on the nature of the catalyst.





TABLE 3. INFRARED ABSORPTION-BAND ASSIGNMENTS

RUN NUMBER	ABSORPTION BAND, cm <sup>-1</sup>	INTENSITY, % Transmittance	ASSIGNMENT*
3	1806	2	R <sub>f</sub> -O-CF <sub>2</sub> -OCF <sub>3</sub>
	1878	1	R <sub>f</sub> -O-CF(CF <sub>3</sub> )COF
	1886	1	
	3618	1	H <sub>2</sub> O
4	1722	<1	No assignment
	1737	<1	
	2050	2	FeF <sub>4</sub> <sup>-</sup> [R <sub>f</sub> CO <sup>+</sup> ]
	3618	2	H <sub>2</sub> O
5	1722	1	No assignment
	1737	1	
	1752	shoulder	R <sub>f</sub> CF <sub>2</sub> COOH
	1766	6	
	1777	shoulder	
	3618	8	H <sub>2</sub> O
9	1777	1.5	R <sub>f</sub> CF <sub>2</sub> COOH
	3618	3	H <sub>2</sub> O
10	1789	1	R <sub>f</sub> -O-CF(CF <sub>3</sub> )COCl
	1806	8	R <sub>f</sub> -O-CF <sub>2</sub> COCF <sub>3</sub>
	1818	8	R <sub>f</sub> -O-CF(CF <sub>3</sub> )COCl
	1878	1	R <sub>f</sub> -O-CF(CF <sub>3</sub> )COF
	1886	1	
	3618	1	H <sub>2</sub> O

\*See text.






Fig. 2. FTIR spectra of the reaction products of perfluoropolyalkylether with Lewis acid catalysts: (a) run 3,  $\text{FeF}_3$ ,  $350^\circ\text{C}$ ; (b) run 4,  $\text{FeF}_3$ ,  $350^\circ\text{C}$ ; (c) run 9,  $\text{AlF}_3$ ,  $350^\circ\text{C}$ ; (d) run 5,  $\text{FeF}_3$ ,  $375^\circ\text{C}$ ; (e) run 10,  $\text{AlCl}_3$ ,  $200^\circ\text{C}$ .

### III. RESULTS AND DISCUSSION

#### A. INFRARED SPECTROSCOPY

The background-subtracted infrared (IR) spectra of the liquid products for runs 3, 4, 5, 9, and 10 are depicted in Fig. 2 and their assignments listed in Table 3. (The IR spectra of the products of runs 1, 2, 6, 6A, 7, and 8 did not exhibit significant degradation-product absorption bands.) Only the 1700 to 2200  $\text{cm}^{-1}$  region is shown because the absorption bands of interest occur primarily in that spectral region, except for an absorption band at 3618  $\text{cm}^{-1}$  that was present in the spectra of all the samples.

The significant spectral bands are of low intensity, indicating that the functional groups responsible for the absorption bands are present in much lower concentrations than the perfluoropolyalkylether functionalities in the product oil. This result is consistent with 1) low levels of reaction or 2) the products being significantly volatile. The first reason is more likely, since very little material was lost in the experimental runs; i.e., less than 10 percent of the oil was lost during reaction.

The spectrum for run 3 exhibits a doublet at 1878 and 1886  $\text{cm}^{-1}$  that has been assigned to  $\text{R}_f\text{-O-CF}(\text{CF}_3)\text{COF}$  (II). Fluorinated acid fluorides absorb in that spectral region ( $\text{CF}_3\text{COF}$ , 1905  $\text{cm}^{-1}$ , and  $\text{CF}_3\text{CF}_2\text{COF}$ , 1890  $\text{cm}^{-1}$ ).<sup>10</sup> The absorption band at 1806  $\text{cm}^{-1}$  can be assigned to  $\text{R}_f\text{-O-CF}_2\text{CO-CF}_3$  (III) by analogy to  $\text{CF}_3\text{COCF}_3$ , 1809  $\text{cm}^{-1}$ .<sup>11</sup> The 3618  $\text{cm}^{-1}$  absorption band most likely reflects the presence of water in the products. The acid fluoride absorption appears as a doublet, 1878 and 1886  $\text{cm}^{-1}$ .  $\alpha$ -halogen substitution has been reported to cause multiple carbonyl absorptions because of conformational isomers,<sup>12,13</sup> or Fermi resonance.<sup>12</sup> The only other possible products that might effect the observed IR spectrum are fluorinated anhydrides—a possibility that can be eliminated because the formation of anhydrides requires the presence of carboxylic acids created from hydrolysis of the acid fluorides (and also the anhydrides). In run 3, no spectral evidence for carboxylic acids was detected.

$\mu$ -Bondagel porous silica columns with ether functionalities that had been bonded to the surface of the solid phase, were 30 cm long and 0.4 cm in diameter and were connected in series. The solvent was Freon TF at a flow rate of 0.3 mL/min. The sample size was 20  $\mu$ L of an approximately 2 weight percent solution administered using a fixed-volume injection loop. A refractive index (RI) detector was used to analyze the column effluent.

TABLE 2. SAMPLE TEST CONDITIONS

RUN NUMBER*	CATALYST	CATALYST WEIGHT, g	MOLE RATIO†	TEMPERATURE, °C	TIME, h
1	FeF <sub>3</sub>	10	0.80	250	24
2	FeF <sub>3</sub>	2	0.16	300	24
3	FeF <sub>3</sub>	2	0.16	350	24
4	FeF <sub>3</sub>	4	0.16	350‡	120
5§	FeF <sub>3</sub>	2	0.16	375	24
6	-	-	-	350	24
6A#	-	-	-	350	24
7	AlF <sub>3</sub>	2	0.22	150	56
8	AlF <sub>3</sub>	2	0.22	250	24
9	AlF <sub>3</sub>	2	0.22	350	24
10	AlCl <sub>3</sub>	2	0.14	200	24

\*10 cm<sup>3</sup> or 18.6 g of perfluoropolyalkylether used in each run except run 4, in which 20 cm<sup>3</sup> of oil was used.

†Moles catalyst/moles perfluoropolyalkylether oil.

‡Reaction temperature exceeded 365°C for several hours.

§Reaction vessel leaked.

||Oil without catalyst.

#Oil without catalyst in previously unused reaction vessel.

#### IV. CONCLUSIONS

Based on our experimental results, the following conclusions can be drawn:

1.  $\text{FeF}_3$  catalysis of the degradation of PFPE can occur at temperatures below those for the onset of thermal degradation.
2. Degradation can cause changes in the PFPE that can ultimately affect the lubricity and lifetime of the lubricant.
3. The catalyzed degradation involves etherate cleavage at both primary and secondary carbons, resulting in acyl halide and ketone degradation products as well as perfluorinated ether products of reduced molecular weight.

The formation of  $\text{FeF}_3$  in catalytic amounts is one of the key steps in our proposed oil-degradation mechanism. Whether  $\text{FeF}_3$  is formed in significant quantities in bearing systems is uncertain, although there were indications it was present in our bearing tests. We plan to verify its formation in future experiments.

## REFERENCES

1. Sianesi, D., Zamboni, V., Fontanelli, R., and Binaghi, M., "Perfluoropolyethers: Their Physical Properties and Behavior at High and Low Temperatures," Wear, 18, pp. 85-100 (1971).
2. Snyder, C. E., Jr., and Dolle, R. E., Jr., "Development of Polyperfluoroalkylethers as High Temperature Lubricants and Hydraulic Fluids," ASLE Trans., 19, 3, pp. 171-180 (1976).
3. Van Dyke Tiers, G., "The Chemistry of Perfluoro Ethers. II. Ether Cleavage with Simultaneous Replacement of  $\alpha$ - Fluorine by Chlorine," J. Amer. Chem. Soc., 77, pp. 6703-6704 (1955).
4. Van Dyke Tiers, G., "The Chemistry of Perfluoro Ethers. III. Synthesis of  $\omega$ -Trichloromethylperfluoroacyl Chlorides by Cleavage of Cyclic Perfluoro Ethers," J. Amer. Chem. Soc., 77, pp. 6704-6706 (1955).
5. Sianesi, D., and Fontanelli, R., "Perfluoro Polyethers. Their Structure and Reaction with Aluminum Chloride," Makromol. Chem., 102, pp. 115-124 (1967).
6. Hudlicky, M., "Chemistry of Organic Fluorine Compounds," MacMillan and Company, New York (1962), p. 266.
7. Paciorek, K. L., Kratzer, R. H., Kaufman, J., and Nakahara, J. H., Determination of Fluorocarbon Ether Autoxidation Degradation Mechanism, SN-8288F, Ultrasonics Inc. (1977) (also AFML-TR-77-150).
8. Chandler, W. L., Lloyd, L. B., Farrow, M. M., Burnham, R. K., and Eyring, E. M., "Titanium Corrosion by a Hot Perfluoropolyether," Corrosion, 36, 3, pp. 152-155 (1980).
9. Gumprecht, W. H., "PR-143--A New Class of High-Temperature Fluids," ASLE Trans., 9, pp. 24-30 (1966).
10. Haszeldine, R. N., "Reactions of Metallic Salts of Acids. Part V. Synthesis of Fluoro-dienes from Fluoro-dicarboxylic Acids," J. Chem. Soc. (London), pp. 4026-4028 (1954).
11. Berney, C. V., "Infrared, Raman, and Near-Ultraviolet Spectra of  $\text{CF}_3\text{CO}_2$  Compounds--II. Hexafluoroacetone," Spectrochim. Acta, 21, pp. 1809-1823 (1965).
12. Dolphin, D., and Wick, A., Tabulation of Infrared Spectral Data, John Wiley and Sons, Inc., New York (1977), p. 316.

13. Barceló, J. R., and Otero, C., "Infra-red Spectra of the Fluorinated Acetic Acids in Condensed and Vapour Phases," Spectrochim. Acta, 18, pp. 1231-1247 (1962).
14. Cook, D., "The Interaction of Friedel-Crafts Catalysts with Organic Molecules," Can. J. Chem., 37, pp. 48-53 (1959).
15. Forsén, S., "A Simple Molecular Orbital Approach to the Effects of Substituents on the Carbonyl Stretching Frequency," Spectrochim. Acta, 18, pp. 595-603 (1962).
16. Berney, C. V., "Infrared, Raman and Near-Ultraviolet Spectra of  $\text{CF}_3\text{COZ}$  Compounds—I. Trifluoroacetyl Chloride," Spectrochim. Acta, 20, pp. 1437-1449 (1964).
17. Ritchie, C. D., and Sager, W. F., "An Examination of Structure-Reactivity Relationships," Prog. Phys. Org. Chem., 2, pp. 323-400 (1964).
18. Brown, H. C., and Okamoto, Y., "Electrophilic Substituent Constants," J. Amer. Chem. Soc., 80, pp. 4979-4987 (1958).
19. Oulevey, G., and Susz, B. P., "Etude de Composés d'Addition des Acides de Lewis. XXII. Exchange du Chlore Radioactif Entre  $\text{AlCl}_3$  et  $\text{C}_6\text{H}_5\text{COCl}$ ," Helv. Chim. Acta, 47, pp. 1828-1832 (1964).
20. Kiet, H. H., Blanchard, L. P., and Malhotra, S. L., "The Gel Permeation Chromatography of Asphalt and the Characterization of Its Fractions in Terms of Molecular and Unit Sheet Weights," Sep. Sci., 12, 6, pp. 627-654 (1977).
21. Dark, W. A., "The Role of HPLC and LC-MS in the Separation and Characterization of Coal Liquefaction Products," J. Chromatogr. Sci., 16, pp. 289-293 (1978).
22. Yau, W. W., Kirkland, J. J., and Bly, D. D., Modern Size-Exclusion Liquid Chromatography: Practice of Gel Permeation and Gel Filtration Chromatography, John Wiley and Sons, New York (1979), p. 178.
23. Hsu, S. M., and Klaus, E. E., "Estimation of the Molecular Junction Temperatures in Four-Ball Contacts by Chemical Reaction Rate Studies," ASLE Trans., 21, 3, pp. 201-210 (1978).

## LABORATORY OPERATIONS

The Laboratory Operations of The Aerospace Corporation is conducting experimental and theoretical investigations necessary for the evaluation and application of scientific advances to new military space systems. Versatility and flexibility have been developed to a high degree by the laboratory personnel in dealing with the many problems encountered in the nation's rapidly developing space systems. Expertise in the latest scientific developments is vital to the accomplishment of tasks related to these problems. The laboratories that contribute to this research are:

Aerophysics Laboratory: Launch vehicle and reentry fluid mechanics, heat transfer and flight dynamics; chemical and electric propulsion, propellant chemistry, environmental hazards, trace detection; spacecraft structural mechanics, contamination, thermal and structural control; high temperature thermomechanics, gas kinetics and radiation; cw and pulsed laser development including chemical kinetics, spectroscopy, optical resonators, beam control, atmospheric propagation, laser effects and countermeasures.

Chemistry and Physics Laboratory: Atmospheric chemical reactions, atmospheric optics, light scattering, state-specific chemical reactions and radiation transport in rocket plumes, applied laser spectroscopy, laser chemistry, laser optoelectronics, solar cell physics, battery electrochemistry, space vacuum and radiation effects on materials, lubrication and surface phenomena, thermionic emission, photosensitive materials and detectors, atomic frequency standards, and environmental chemistry.

Computer Science Laboratory: Program verification, program translation, performance-sensitive system design, distributed architectures for spaceborne computers, fault-tolerant computer systems, artificial intelligence and microelectronics applications.

Electronics Research Laboratory: Microelectronics, GaAs low noise and power devices, semiconductor lasers, electromagnetic and optical propagation phenomena, quantum electronics, laser communications, lidar, and electro-optics; communication sciences, applied electronics, semiconductor crystal and device physics, radiometric imaging; millimeter wave, microwave technology, and RF systems research.

Materials Sciences Laboratory: Development of new materials: metal matrix composites, polymers, and new forms of carbon; nondestructive evaluation, component failure analysis and reliability; fracture mechanics and stress corrosion; analysis and evaluation of materials at cryogenic and elevated temperatures as well as in space and enemy-induced environments.

Space Sciences Laboratory: Magnetospheric, auroral and cosmic ray physics, wave-particle interactions, magnetospheric plasma waves; atmospheric and ionospheric physics, density and composition of the upper atmosphere, remote sensing using atmospheric radiation; solar physics, infrared astronomy, infrared signature analysis; effects of solar activity, magnetic storms and nuclear explosions on the earth's atmosphere, ionosphere and magnetosphere; effects of electromagnetic and particulate radiations on space systems; space instrumentation.



**END**

**FILMED**

**7-85**

**DTIC**